



CITY OF CARSON, CA
MEMBER NO. 38521

QUOTATION
NO. 9142 R

DATE: 2/13/2018
TERMS: NET 30
F.O.B: FRESNO
MFG PRODUCT: 90 DAYS ARO
INSTALL: 90 DAYS AROT

QTY	PART NO.	DESCRIPTION	PRICE	EXTENSION
		<u>PB LOADER CONTRACT NO. 052417-PBL</u> <u>NJPA CONTRACT - LISTED PRICES</u>		
1	L-250-CT	TRUCK MOUNTED LOADER: MODEL L-250-CT PB LOADER, 1 1/2 CUBIC YARD SHOVEL, HEAVY DUTY, CLAM SHELL WITH TILTING ACTION ON SHOVEL, 5,000 LIFTING CAPACITY., CAB SHIELD AND FREE STANDING BULKHEAD WITH HYDRAULIC LATCHES, INSTALLATION AND PAINT		\$98,248.00
1	1975-1B	BOLT- ON CARBIDE BLADE		\$1,624.00
1	1975-51	WELD ON CARBIDE BLOCKS PACKAGE		\$1,443.00
1	7425-00	AIR OPERATED AUTOMATIC MIRRORS		\$2,270.00
1	PBLDB-09	DUMP BODY INSTALLATION: PB LOADER SUPPORT BODY, 14 FT 12-14 YARD, HPT53-120 CLASS 80 NTEA HOIST, 3/16" STEEL FLOOR AND TAILGATE, 10 GAUGE STEEL BALANCE, 42" SIDES, 54" FRONT AND 46" REAR, 12" SPREADER APRON, 1/4 CABSHIELD, LED LIGHTS, WIRING HARNESS & BACKUP ALARM, PUMP, CONTROLS, TANK, VALVE, MUD FLAPS, STEEL MUDGUARDS, HOT SHIFT PTO, AIR TAILGATE, PAINT BLACK, INSTALLATION.		\$29,230.00
1	50501-00	PULL TARP 16' - ASPHALT W/ ROPE HOOKS (5 PER SIDE)		INCLUDED
2	393-00	PULL LADDER EZ-STEP - MOUNTED DRIVER & PASSENGER SIDE OF BODY		INCLUDED
1	2014-00	SIDE BOARDS WOOD W/ LINSEED OIL		INCLUDED
1	MODS-35	DUAL CONNECTED BODY PROPS		INCLUDED
2	7000-48	TOOL BOX 48"	\$529.00	\$1,058.00
1	7999-10	FIRE EXTINGUISHER 5#		\$209.00
1	7999-40	TRIANGLE KIT		\$34.00
1	MODS-37	ECCO EC7000-K BACKUP CAMERA SYSTEM (MONITOR + 1 CAM) WITH SOUND ON MONITOR & MICROPHONE ON CAMERA		\$1,217.00
1		<u>NON-NJPA LISTED OPTIONS</u> 1/4" AR 450 FLOOR (IN LIEU OF 3/16" HI TENSILE ABOVE)		INCLUDED
1		AIR HIGH LIFT TAILGATE (IN LIEU OF MANUAL)		INCLUDED
1		GRIP STRUT CAT-WALK FOR BODY, BOTH SIDES		INCLUDED
1		SET OF HARD WOOD RUB RAIL BOARDS		INCLUDED
1		BODY PROPS AND AND LADDERS PAINTED HIGH VISIBILITY YELLOW		INCLUDED
1		WHELEN TACF85LH LED TRAFFIC ADVISOR, 45.12" LG WITH DEBRIS SHIELD RECESSED INTO TOP OF TAILGATE		\$2,126.00
2		GO-LITE MODEL 2057 WORK LIGHTS MOUNTED REAR WITH REMOTE CONTROL	\$782.00	\$1,564.00
1		2018 AUTOCAR ACX42 CNG CHASSIS 80 DGE BACK OF CAB FUEL SYSTEM		\$183,466.00
		TOTAL NET PRICE, LESS FREIGHT AND TAX:		\$322,489.00
		CALIFORNIA LICENSE FEE:		\$65.00
		SALES TAX (CARSON 9.5%):		\$30,636.46
		CALIFORNIA TIRE RECYCLE FEE:		\$10.50
		TOTAL NET PRICE, LESS FREIGHT:		\$353,200.96
		NOTES: 1. LEAD TIME FOR LOADER & DUMP BODY PRODUCTION AND INSTALLATION IS 180 DAYS AFTER RECEIPT OF ORDER; 90 DAYS FOR PRODUCTION AND 90 DAYS FOR INSTALL. 2. REQUIRED CAB TO TRUNNION IS 141 INCHES. 3. BACKUP ALARM PROVIDED WILL BE AN ECCO MODEL SA90N. Delivery times are approximate.		

EXHIBIT NO. 2

PAGE 4

PB Loader Corporation

5778 W. Barstow • Fresno, California 93722-5024 • Telephone (559) 277-7370 • Fax (559) 277-7375

Toll free 800-350-8521 • Web www.pbloader.com